सत्यमेव जयते

लोक निर्माण विभाग
PUBLIC WORKS DEPARTMENT
दूरभाष/ Phone:+91-11-23317926/23766924
ई-मेल/e-mail: prcempwddelhi@gmail.com

दिल्ली सरकार
PWD

अपर महानिदेशक (अनुरक्षण एवं सेतु)
लोक निर्माण विभाग (दिल्ली सरकार)
12वीं मंजिल, बहुमंजिला भवन
आई.पी. एस्टेट, नई दिल्ली-110002

स्वच्छ भारत
एक कदम स्वच्छता की ओर

Addl. Director General (Maint. & Flyover)
Public Works Department (GNCTD)
12th Floor, MSO Building
I.P. Estate, New Delhi -110002

फ. स. 23(52)/अपर महानिदेशक (अनु. एवं सेतु)/लो.नि.वि./2025/**1801** दिनांक: **24.12.2025**

OFFICE MEMORANDUM

Sub: Enhancing Safety of Road Users in Foggy Weather - reg.

In the Winter Season due to Foggy Conditions, there is reduced visibility experienced on PWD, GNCTD roads. This situation poses a significant risk to Road users particularly during the night time, leading to potential accidents and endangering the safety of Road users. In order to improve the visibility and enhancing the safety of Road users, all field units are directed to undertake following mitigation measures:

i. Rectify the faded or inadequate pavement markings such as Edge line, Lane line, Chevron markings, Zebra markings etc.
ii. Enhance visibility of road safety devices viz. MBCB/ RCC barrier by providing reflective markers, fixing retro reflective yellow sticker 50 mm x 50 mm on each post of mettle beam safety barrier etc.
iii. Provide Roadway Delineators confirming to clause 3 of IRC-79, 2019.
iv. Fix Median Markers as per section 4 of IRC 79, 2019 on medians and RCC Barriers @ 2m distance in case of urban areas and @ 5m distance in case of rural areas of roads.
v. Provide Transverse bar markings with could applied plastics of thickness 5mm and 10 mm in Habitations area and accident-prone locations as per IRC 35.
vi. Street lighting wherever installed shall be made operational and light shall be switch on early as per the foggy weather conditions.
vii. Provide Solar Blinkers on Median openings.
viii. Provide Zebra markings on all Median Openings and road studs on Zebra marking confirming to clause: 9.5 of IRC: SP-84/87.
ix. Replacement of damaged/missing Hazard Object Hazard Markers signs at diverging & merging locations, Road Side Hazards, Culverts etc.

Contd....2/-

24/12

x. Provide missing/damaged road signs including Chevron signs on curves as per IRC-67 2022.

xi. To enhance the visibility, replace damaged/missing road studs along edge lines and centre line on curves, slip roads of intersections, Zebra markings etc. confirming to table 9.1 of IRC SP 87/84 2019.

xii. On construction stretches, safety measures on diversions shall be provided such as paved diversion pavement markings road studs, barricading, diversion signs, solar blinkers etc. confirming to IRC: SP-55.

xiii. All Officials/Supervisors/Workers to wear reflective jackets during their visit/ undertaking any activity on Roads.

24.06.2025

(PRADEEP GUPTA)
Addl. Director General (M&F)

Copy:

1. OSD to Hon'ble Minister (PWD), GNCTD.
2. PS to ACS (PWD), GNCTD.
3. SS-I, PWD, GNCTD.
4. SS-II, PWD, GNCTD.
5. E-in-C, PWD, GNCTD.
6. All CEs (Maintenance), SEs (Maintenance) & EEs (Maintenance), PWD, GNCTD for strict compliance.
7. PWD website