CH. 2650 | CH. 2600 | CH. 2550 | CH. 2500

CH. 2650 | CH. 2500

| AREA CALCULATION(CH-3300TO 3650) | | | | |
|---|---|---|---|---|
| SNO. | LEGEND | MATERIAL | LOCATION | AREA (m²) |
| 1 | | GREEN PLANTING | OVERALL | 788.536 |
| 2 | | 80 MM THK. PAVER BLOCKS | VEHICULAR MULTIMODAL | 145.94 |
| 4 | | CONCRETE | RAMP/SLOPE | 130.68 |
| 5 | | M30 GRADE CONCRETE | CYCLE TRACK | 1110.46 |
| 6 | | 60 MM THK. PAVER BLOCKS | PEDESTRIAN PATHWAY/MINOR VEHICULAR ENTRY | 2953.37 |
| 7 | | 60 MM THK. PAVER BLOCKS | PEDESTRIAN REFUGE ISLAND | 345.98 |
| 8 | | THERMOPLASTIC PAINT | PEDESTRIAN CROSSING & LANE MARKING(100mm THK) | 300.00 |
| 9 | | THERMOPLASTIC PAINT | CYCLE CROSSING | 851.99 |
| 10 | | TAR | ROAD | 7222.84 |
| 11 | | COBBLE STONE | SERVICE ROAD | 380.481 |

EXISTING PATHWAY EDGE

- TOTAL NO. OF BOLLARDS AROUND THE T-JUNCTION= 87
  TOTAL BOLLARDS FOR 05 JUNCTIONS= 440

| KERB LENGTH CALCULATION(CH-3300 TO 3650) | | | | |
|---|---|---|---|---|
| SNO. | KERB | LEGEND | TYPE | LENGTH(m) |
| 1 | | | TYPICAL ROAD EDGE KERB 300mm HIGH | 425.92 |
| 3 | | | FLUSH KERB 150mm THK 300mm HIGH | 848.79 |
| 4 | | | MEDIAN KERB 150mm THK 450mm HIGH | 647.37 |
| 5 | | | TYPICAL KERB 150mm THK 300mm HIGH | 655.65 |

Delhi Metro Land

E D Block Market

Park

Metro Parking

PATHWAY
2.5 MT WIDE CYCLE TRACK
3.3 mt BUS LANE
3.1 mt MV LANE
2.5%SLOPE DN
REFUGE ISLAND
STOP
BUS STOP
3.3 mt BUS LANE
3.1 mt MV LANE
3.3 mt BUS LANE

KEY PLAN:

scale 1 : nts

NOTES & INFORMATION
1. ALL DIMENSIONS AND LEVELS ARE INDICATED IN MILIMETERS.ONLY FIGURED DIMENSIONS ARE TO BE CONSIDERED.
2. DIMENSIONS TO BE READ AND NOT MEASURED.

THIS DRAWING IS THE PROPERTY OF OASIS DESIGNS INC., AND IS NOT TO BE COPIED / REPRODUCED WITHOUT PRIOR PERMISSION.

REVISION | DATE

CLIENT: PWD, NORTH DELHI

PROJECT: STREETSCAPING OF PWD ROADS - RITHALA ROAD FROM WAZIRPUR JUNCTION TO RITHALA METRO STATION

STAGE: TENDER DRAWING

SURVEYOR: Geotechnical Consultants & Land Surveyors 91-D-3, Street 1, East Moti Bagh, Old Rohtak Road, Delhi -110007. Ph : 25866806, 25851434, Fax-25851434 Mob.-9811108174, 9310502426 E-mail:- laxmanngg@rediffmail.com

PHE CONSULTANTS: TECHNO ENGINEERING CONSULTANTS B4/3, POCKET-A, SIDDHARTHA EXTENSION, NEW DELHI-110014 TELEFAX : 26344958 E-MAIL: tech.ec@vsnl.com, mb_ec@yahoo.co.in

ELECTRICAL CONSULTANTS: ENGINEERING CONSULTANTS N-17,Ajan Bagh, Farm Houses,Nr.Dhamshi Talab Andheria Mor,Mehrauli NEW DELHI-110030,TELEFAX : 011-26844831 E-MAIL: engpant27@gmail.com, gopant27@gmail.com

IRRIGATION CONSULTANTS: SUMMERDROP ENGINEERING PVT LTD. 87,N.I.T. INDUSTRIAL AREA, JHILMIL, NEW DELHI-110052 TEL-42160071/2,46560715/62

TRANSPORT & NMT CONSULTANT: SGArchitects, New Delhi. website: www.sgarchitects.in

STREETSCAPE CONSULTANT: OASIS DESIGNS INC
Architecture . Landscape . Urban Design
317/2, SEC-A, PKT-B, VASANT KUNJ, NEW DELHI-70, PH: +91-11-26122344, email : mail@oasisdesigns.org
Website : www.oasisdesigns.org

TITLE: AREA CALCULATION AND KERB LENGTHS

SUB TITLE: MADHUBAN CHOWK JUNCTION
CH 2500 - CH 2650

DWG. No. PWD_TD_05

DATE: 25-11-16 | DRAWN

SCALE: 1:600 | CHECKED